



	FINISHED SQ. FT.	UNFINISHED SQ. FT.
BASEMENT	1,688	540
MAIN FLOOR	2,317	1,372
2ND FLOOR	1,593	100
		DECK 370
		POOL HOUSE 337
TOTAL	5,598	2,719

- FOUNDATION & FRAMING NOTES**
- All structural members and framing members shall be confirmed by contractor, sub-contractor, and/or supplier for size, spacing, and species to verify they meet local code requirements.
 - 8"x9" high poured concrete foundation walls, unless otherwise noted.
 - 2x6 exterior and 2x4 interior walls, unless otherwise noted.
 - All exterior headers shall be (2) 2x12, unless otherwise noted.
 - Pella window sizes noted. Contractor, sub-contractor, and/or suppliers to confirm window openings for egress, min. light, min. height, and ventilation requirements. Contractor and/or sub-contractor to go off of supplier provided rough opening sheet for all rough openings.
 - Ceiling Heights: 10' 1-1/8" Main Floor, 8' 1-1/8" Second Floor, unless otherwise noted.
 - All interior framing dimensions to framing edge, unless otherwise noted.
 - Allow for at least 3.5" from interior door rough openings to wall.
 - All angled walls are 45°, unless otherwise noted.

BASEMENT/FOUNDATION PLAN
SCALE: 1/4" = 1'-0"

NUMBER	DATE	REVISION TABLE	DESCRIPTION

PROJECT LOCATION:

PREPARED FOR:

REVISION TABLE

PROJECT LOCATION:

PREPARED FOR:

VIRTUACTIVE
 VirtuActive - 3D Drafting & Design
 331 Village Pointe Plaza, Suite 303, Omaha, NE 68118
 www.virtuactive.com | 402.379.8100
 Designed by: Tony Eila | Tony@virtuactive.com